

## GENERAL NOTES

STRUCTURE WALL THICKNESS TO BE 8" BRICK, 6" CONCRETE BLOCK, 9" GRADE "A" CONCRETE OR 5" PRECAST REINFORCED CONCRETE, OR COMBINATIONS OF ABOVE AS DIRECTED BY THE ENGINEER.

REINFORCEMENT FOR 5" PRECAST REINFORCED CONCRETE SHALL BE 6" X 6" W16 X W16 WELDED STEEL WIRE FABRIC AND SHALL BE EMBEDDED 2" CLEAR.

PRECAST INLET UNITS SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF AASHTO DESIGNATION M199.

PRECAST CONCRETE FLAT SLAB TOP MAY BE USED ON THE STRUCTURE. THE TOP SHALL BE INSTALLED ON BED OF MORTAR.

